



DEPARTMENT OF THE NAVY NAVY EXPERIMENTAL DIVING UNIT PANAMA CITY, FLORIDA 32407-5001

IN REPLY REFER TO:
NAVSEA TA 91-002

AD-A243 535



NAVY EXPERIMENTAL DIVING UNIT

REPORT NO. 10-91

EVALUATION OF BAUER HIGH PRESSURE BREATHING AIR P-2 PURIFICATION SYSTEM

GEORGE D. SULLIVAN

AUGUST 1991

DISTRIBUTION STATEMENT A: Approved for public release; distribution is unlimited.

Submitted:

G.D. SULLIVAN

GS-11

Test Director

Reviewed:

J.W. McCARTHY

GM-14

Hyperbaric Engineer

Approved:

JAMES E. HALWACHS

CDE, U.S. Navy

Commanding Officer

B.K. MILLER, JR.

LCBR USN

Senior Projects Officer

J.B. McDONEL

LCDR, USN

Executive Officer

91-15413

	REPORT DOC	UMENTATIO	N PAGE				
1a. REPORT SECURITY CLASS UNCLASSIFIED	SIFICATION	1b. RE	STRICT	IVE MARKINGS		,	
2a. SECURITY CLASSIFICATI	ON AUTHORITY	3. DI	STRIBU	TION/AVAILABI	LITY OF	REPOR	RT
2b. DECLASSIFICATION/DOWN	IGRADING SCHEDULE						
4. PERFORMING ORGANIZATI NEDU Report #10-91	ON REPORT NUMBER(S)	5. MC	NITORI	NG ORGANIZATI	ON REPOR	T NUM	BER(S)
6a. NAME OF PERFORMING OR Navy Experimental Diving			ME OF	MONITORING OR	GANIZATI	ON	
6c. ADDRESS (City, State, Panama City, Florida 3240		7b. AD	DRESS	(City, State,	and ZIP	Code)
8a. NAME OF FUNDING/SPONS ORGANIZATION Naval Sea Systems Command	(If applicable		OCUREM	ENT INSTRUMEN	T IDENTI	FICAT	ION NUMBER
8c. ADDRESS (City, State,	and ZIP Code)	10. so	JRCE O	F FUNDING NUM	BERS		
Washington, D.C. 20362-51	01	PROGRA ELEMEN	-	PROJECT NO.	TASK NO 91-0		WORK UNIT ACCESSION NO.
11. TITLE (Include Securi Evaluation of BAUER High	ty Classification) Pressure Breathing Air P-	2 Purific	ation	System.	•		
12. PERSONAL AUTHOR(S) Mr. David Sulliven							
FINAL	13b. TIME COVERED FROM TO	1	DATE		ar,Month	,Day)	15. PAGE COUNT
16. SUPPLEMENTARY NOTATION							
17. COSATI CODES 18. SUBJECT TERMS (Continue on reverse if necessary and identify						dentify	
FIELD GROUP SUB	B-GROUP by block num						
BAUER High Pressure Breathing Air P-2 Purification System							
19. ABSTRACT (Continue on In response to NAVSEA thigh Pressure, Breathing test was to determine if by the U.S. Navy. Additional addit to the Approved fospecifications for quantiful the design and engineering considered suitable for under the second suitable for under the seco	asking, Navy Experimental Air Purification System f the P-2 Air Purification onally, if the system pasor Navy Use (ANU) list. It of air processed with my were determined to be a	Diving U rom 16 Ju System fu sed the t he BAUER a quality dequate.	nit (Ni ly 199 nction est cr 2-2 Pu which The B	EDU) tested to 1 to 19 July of ed as specific iteria a recon rification Sys met U.S. Nav AUER P-2 Air I	1991. The dand water mendation of the metry purity Purifical	he pu as su on wo the stan	itable for use buld be made to manufacturer's idards.
20. DISTRIBUTION/AVAILABI	LITY OF ABSTRACT	T10	21.	ABSTRACT SECU	RITY CLA	SSIFI	CATION
22a. NAME OF RESPONSIBLE		т	PHONE	(Include Area	a Code)	22c.	OFFICE SYMBOL
		L				<u> </u>	

CONTENTS

												,	age	NO.
I.	INTRO	DUCTI	ON		• • • •	 	• • •	 	 	 			· • • •	1
II.	EQUII	PMENT	DESCR	IPTION	• • • •	 	• • •	 	 	 	• • • •			. 1
	A.	PURIE	CATI	ON SYS	TEM.	 	• • •	 	 	 		·		. 1
	В.	COMPR	RESSOR		• • • • •	 	• • •	 	 	 				. 1
III.	TEST	PROCE	EDURE.			 		 · • • •	 	 	• • • •			1
IV.	ENDUF	RANCE	TEST 1	RESULT	s	 	• • •	 	 	 	• • • • ·			. 6
٧.	CONCI	LUSION	ıs			 	• • •	 	 	 	• • • •		. .	. 6
VI.	RECON	I MENDA	TIONS			 		 	 	 				7
VII.	REFER	RENCES	;		• • • • •	 	• • •	 	 	 • • • •	• • • •			. 8
APPENI	A XIC	- Tes	t Log		• • • •	 		 	 	 	.A-1	thi	u A-	4
APPENI	OIX B	- Air	: Samp	le Res	ults.	 	• • • •	 	 	 	.B-1	thi	ru B-	. 3



Acous	194ca Fe	F	
57.	GRAAI		4
DTIC	TAB		
والمعطوا) इन्स्राधन्त्र		
3430	krjea ti c	A1	
- **	ribution ilabisi [Aveil	Ly Co	
Dist	Epsc	ial	
A-I			

ILLUSTRATIONS

Figure No	<u>.</u>	Page No.
1	P-2 Purification Panel View	2
2	Bauer Purification System Ambient Temperature Correction	3
3	Bauer P-2 Test Configuration	5

I. INTRODUCTION

In response to NAVSEA tasking¹, the BAUER P-2 high pressure breathing air purification system, Figure 1, was tested² by NEDU. The test determined if the purification system would provide suitable breathing air and a service life satisfying the U.S. Navy requirements for use with divers air supply compressors. Charge rates were taken to calculate total cubic feet of air processed each day.

II. EQUIPMENT DESCRIPTION

A. PURIFICATION SYSTEM

The purification system consists of two cylinders. The upstream cylinder contains a molecular sieve and is a coalescing type separator that removes oil and water vapors suspended in the compressed air. The molecular sieve is made to adsorb oil and water vapors. The downstream cylinder contains a cartridge with hopcalite and activated charcoal. The hopcalite converts carbon monoxide (CO) to carbon dioxide (CO). The activated charcoal removes odors, taste and fluorocarbons.

A pressure maintaining/non-return valve is provided downstream from the purification system to ensure that a 2000 psig pressure build-up occurs in the cylinders during compressor start-up. This provides for optimum filtering, moisture separation, and prevents compressed air return from the charged air storage flasks to the compressor during unit shutdown.

A manual condensate drain valve is located on the bottom of the separator cylinder and a relief valve is mounted on top. A system bleed off valve is located next to the pressure maintaining valve.

The P-2 purification system is rated to process 40,000 cubic feet of free air at 70°F. Maximum air flow is 40 cubic feet per minute (cfm) of free air at 5000 psig. The manufacturer provides a correction factor to assist in determining the service life of the cartridge when operated at other than 70°F. Figure 2 is a line graph of the correction factors.

B. COMPRESSOR

The compressor used for this test was a Bauer K-20 four-cylinder, four-stage, reciprocating, air-cooled unit. The compressor is rated to deliver 20 cfm of free air at 5000 psig.

III. TEST PROCEDURE

The Bauer Purification System's instruction pamphlet³ was used to conduct an initial inspection of the equipment to ensure receipt of all parts and material. Inspection consisted of verifying that all instruments and controls were clearly and permanently marked, gauges were easily viewed, and controls easily operated.




FIGURE 1: P-2 PURIFICATION PANEL VIEW




FIGURE 2: BAUER PURIFICATION SYSTEM AMBIENT TEMPERATURE CORRECTION

The compressor configured with the P-2 Purification system was operated at no load prior to starting the actual test. No load conditions were with the vents open and the back pressure valve set at 2000 psig. An air sample was taken at two hours.

The purification unit and ancillary equipment were set up in accordance with the test plan2. A line diagram of the test configuration is depicted in The unit was placed in an exterior work area open to ambient temperature but protected by an awning from direct weather. A Digitech HT series, model 5820 temperature monitor and two Yellow Springs Instruments, 6700 series thermistor probes were attached to measure compressor discharge and ambient temperatures. Ambient temperatures were recorded on an hourly basis and averaged each day and again for the overall test period. This overall test period average was was used to determine the manufacturer's correction factor in order to calculate corrected life expectancy of the purification cartridge. A Cole Parmer humidity indicator, model 3310-20 was mounted near the compressor unit and the humidity recorded hourly. An MSA Toxgard carbon monoxide (CO) monitor with a flow range from 350 to 900 cc per minute was used to analyze compressor discharge air samples before and after the purification system. One hundred percent nitrogen (N2) and 101 parts per million (ppm) CO in air were used to calibrate the monitor on a daily basis. The gases were fed through a Victor Equipment Co. 4000 psig manual regulator to a Fischer/Porter flow meter and into the monitor sensor. Carbon monoxide was introduced directly into the compressor intake through a Victor Equipment Co. 4000 psig manual regulator and Fischer/Porter flow meter. The introduction of CO was adjusted to maintain 50 ppm at the entrance of the filtration system. The compressor and purification system were operated daily to charge four 2250 cubic inch floodable volume The four cylinders were interconnected to simulate one large air When 2000 psig flask pressure was reached the vent was adjusted to allow the compressor to maintain the 2000 psig while continuously running. An arrangement of tubing provided a method to supply a gas sample from before or after the filter to the CO monitor. Shifting from clean side to contaminated side of the purification system was done approximately every 30 minutes to allow the monitor time to settle out between readings. Hourly CO readings are in Appendix A.

After five hours of operation, the unit was secured with 1500 psi in the volume tanks. All vents, flowmeters, and blowdown valves were closed. The unit remained secured until 0700 the following day. The pressure drop was less than 100 psig and was considered insignificant when temperature differentials were considered.

The NEDU test $plan^2$ contains the pass/fail criteria used during the evaluation. Appendix A is the test log and contains the recorded data.




FIGURE 3: BAUER P-2 TEST CONFIGURATION

IV. ENDURANCE TEST RESULTS

Total volume of processed air was verified by charging from 1000 to 2000 psig daily. The following parameters were recorded throughout the 26 hours of operation:

(1) Date

(2) Time

(3) Total meter hours

(4) Total test hours

(5) Ambient Humidity

(6) Ambient Temperature

(7) Engine oil pressure

(8) Engine head temperature

(9) Amperage

(11) Compressor oil level

(12) Compressor oil pressure

(13) Discharge line pressure

(13) Discharge line temperature

(14) CO before filter

(15) CO after filter

The volume of air delivered and the time to achieve that volume was logged daily (Appendix A). The purification system processed a total of 33,135 cubic feet of air. Using the correction factor provided by the manufacturer, the total cubic feet of air processed equaled 133% of the expected active life of the purifier cartridge. The data collected provided a complete operational and maintenance log for this test and was the basis for computing and evaluating all the test results.

NOTE: On days one and two of the test, the charge rate times were excessive and the throttle was adjusted on the diesel engine to increase the speed and CFM.

Air samples were taken from the purification system discharge at test hours 2, 15 and 26 for purity analysis by Naval Coastal System Center Laboratory, Code 5130. Results are located in Appendix B. All samples were within established limits until the 26 hour sample.

Maintenance consisted of a new purification cartridge, No. 058827, being installed prior to commencing the test. All gauges and indicator readings were checked and considered to be within normal limits. No other maintenance was required.

V. CONCLUSIONS

- 1. The BAUER P-2 Purification System delivers acceptable breathing air at a capacity which exceeds the manufacturer's specifications.
 - 2. The unit is sturdy and readily maintained.
- 3. The BAUER P-2 Purification System removes carbon monoxide from contaminated air sources and delivers air of a quality that exceeds required purity standards⁴ until the 26 hour sample.
- 4. The BAUER P-2 Purification System is suitable for use by the U.S. Navy.

VI. RECOMMENDATIONS

The Vendor and NAVSEA should be contacted prior to purchase to ensure the unit meets the user's needs.

If the user is concerned about CO contamination of an air supply, the incorporation of a CO analyzer in conjunction with a purification system should be considered, and is highly recommended by NEDU.

VII. REFERENCES

- 1. NAVSEA Task 91-002; Evaluation of commercially available filters for high pressure and low pressure breathing air.
 - 2. NEDU Test Plan No. 91-24 Bauer P-2 Purification system Evaluation.
- 3. Bauer COmpressors Inc. P-2 Purification System Instruction Pamphlet dated November 11 1989 BAUER Compressors Inc 1326 Azalia Garden Road Norfolk Va 23502.
- 4. U.S. Navy Diving Manual, Vol. 1, NAVSEA 0994-LP-001-9010, Air Purity Standards revision 2 December 15 1988 paragraph 5.3.2.

APPENDIX A
TEST LOG
BAUER P-2 PANEL MOUNTED
PURIFICATION SYSTEM EVALUATION

						3310	DIESEL ENGINE				COMP	COMPRESSOR			
1991 DATE	REAL TIME	TOTAL METER HOURS	TOTAL TEST HOURS	AMBIENT HUMIDITY	AMBIENT TEMPERATURE	OIL PRESSURE	ENGINE HEAD TEMPERATURE	AMPERAGE	OIL	O1L PRESSURE	DISCHARGE LINE PRESSURE	DISCHARGE Line Temperature	CARBON MC BEFORE FILTER	MONOXIDE AFTER FILTER	3 2 2
7-16	0630	105.2	00.00	80%	83.8°F	100	160°F	0	FULL	825	2000	66.0°F	Mdd 0	0	¥dd
2-16	1000	105.7	00.30	67X	89.2°F	06	160°F	0	FULL	850	2000	83.5°F	Mdd 0	0	Mdd
2-16	1030	106.2	01.00	209	89.8°F	%	160°F	0	FULL	750	2000	98.2°F	85 PPM	0	PPK
7-16	118	106.7	01.30	26%	91.9°F	90	160°F	0	FULL	800	2000	99.1°F	52 PPM	0	Mdd
7-16	1100	SHUT	DOWN THE	SHUT DOWN THE TESTING FOR LUNCH	R LUNCH										
7-16	1230	106.7	01.30	272	85.8°F	06	160°F	0	FULL	850	2000	86.7°F	53 PPM	0	Wdd
7-16	1300	107.2	05.00	64x	91.3°F	06	160°F	0	FULL	800	2000	95.3°F	S6 PPM	0	M d
2-16	1100	CAPTU	RED A FI	CAPTURED A FILTER DISCHARGE AIR	S	IPLE FOR ANALYSIS	s								
7-16	1330	107.7	02.30	279	91.2°F	8	160°F	0	FULL	850	1525	98.7°F	58 PPM	0	Mdd
7-16	1330	SECUR	ED TEST	SECURED TESTING FOR THE DAY)AY										
								COMMENTS	ITS						

0900 CALIBRATED THE CARBON MONOXIDE MONITOR
THE COMPRESSOR MOISTURE SEPARATORS AND THE FILTER PANEL COALESCING FILTER MUST BE BLOWN DOWN EVERY 15 MINUTES
1000 CHARGE RATE WAS TAKEN. IT TOOK 20.4 MINUTES TO CHARGE FROM 1000 PSIG TO 2000PSIG...COMPRESSOR SPEED WAS INCREASED
1325 CHARGE RATE WAS TAKEN. IT TOOK 19.6 MINUTES TO CHARGE FROM 1000 PSIG TO 2000PSIG...COMPRESSOR SPEED WAS INCREASED AGAIN.
AVERAGE TEMPERATURE FOR 7-16 - 89.0°F AIR PROCESSED FOR 7-16--18.3 CFM x 1.5 x 60 = 1647 TOTAL CUBIC FEET

APPENDIX A TEST LOG BAUER P-2 PANEL MOUNTED PURIFICATION SYSTEM EVALUATION

						DIES	DIESEL ENGINE				COMP	COMPRESSOR			
1991 DATE	REAL TIME	TOTAL METER HOURS	TOTAL TEST HOURS	AMBIENT HUMIDITY	AMBIENT TEMPERATURE	OIL PRESSURE	ENGINE HEAD TEMPERATURE	AMPERAGE	OIL LEVEL	OIL PRESSURE	DISCHARGE LINE PRESSURE	DISCHARGE Line Temperature	CARBON MONOXIDE BEFORE AFTER FILTER FILTE	AF AF FI	IOXIDE AFTER FILTER
7-17	0700	107.7	2.5	206	75.8°F	95	150°F		FULL	890	1800	77.2*	Wdd 0	0	Mdd
7-17	080	108.7	3.5	89%	79.0°F	06	150°F		FULL	850	1900	85.3°F	72 PPM	٥	Mg
71-7	9060	109.7	4.5	82%	82.2°F	06	150°F		FULL	850	2000	87.6°F	81 PPM	0	M M
71-7	1000	110.7	5.5	80%	80.4°F	06	150°F		ומרר	850	2000	87.7°F	M94 49	٥	Mdd
71-7	1100	111.7	6.5	83%	80.7°F	06	150°F		רטנו	850	2000	88.8*	56 PPM	0	₩ dd
71-2	1200	112.7	7.5	85%	81.8*F	8	150°F		FULL	850	2000	92.8°F	54 PPM	٥	P P
7-17	1300	113.7	8.5	89%	80.6°F	8	150°F		FULL	850	1700	89.6°F	58 PPM	0	¥ dd
7-17	1400	114.7	9.5	93%	76.3°F	06	150°F		נחרר	850	2050	87.8°F	Wdd 79	0	Mdd
71-7	1430	115.2	10.0	92%	77.3°F	8	150°F		FULL	850	2050	86.5°F	62 РРМ	-	Md
	_														
	_														
<u> </u>															
			_												
	-	_													
0700 (0910 (1305 (AIR PE AVERAGE	CALIBRAT CHARGE R CHARGE R ROCESSED ROCESSED	0700 CALIBRATED CARBON MONOX 0910 CHARGE RATE WAS TAKEN. 1305 CHARGE RATE WAS TAKER. AIR PROCESSED 7-15 = 19.7 CF AIR PROCESSED TO DATE = 9360 AVERAGE TEMPERATURE FOR 7-15	0700 CALIBRATED CARBON MONOXI 0910 CHARGE RATE WAS TAKEN. 1305 CHARGE RATE WAS TAKER. AIR PROCESSED 7-15 = 19.7 CFV AIR PROCESSED TO DATE = 9360 AVERAGE TEMPERATURE FOR 7-17	DE MONITOR 11 TOOK 16 11 TOOK 16 1 X 2 X 60 CF + 1647 = 79.3*F	3.2 MINUTES TO C 5.9 MINUTES TO C + 21.2 CFM x 5. = 11007 TOTAL C	HARGE FROM HARGE FROM 5 x 60 = 93 UBIC FEET	TO CHARGE FROM 1000 PSIG TO 2000 PSIG TO CHARGE FROM 1000 PSIG TO 2000 PSIG X 5.5 x 60 = 9360 TOTAL CUBIC FEET TAL CUBIC FEET	000 PSIG 000 PSIG FEET	COMMENTS	NTS					

APPENDIX A TEST LOG BAUER P-2 PANEL MOUNTED PURIFICATION SYSTEM EVALUATION

							PUKIFICALION STSIEM EVALUALION	STSIEM EVA	FOX 1 FOX						
						TESET	SEL ENGINE				д	COMPRESSOR			
1991 DATE	REAL	TOTAL METER HOURS	TOTAL TEST HOURS	AMBIENT HUMIDITY	AMBIENT TEMPERATURE	O1L PRESSURE	ENGINE HEAD TEMPERATURE	AMPERAGE	LEVEL OIL	OIL PRESSURE	DISCHARGE LINE PRESSURE	DISCHARGE LINE TEMPERATURE	CARBON MO BEFORE FILTER	MONOXIDE AFTER FILTER	
7-18	0630	115.2.	10.01	91%	78.5°F	06	150°F	\$+	FULL	850	2000	79.2°F	Mdd 0	Mdd 0	
7-18	0730	116.2	11.0	89%	80.3°F	06	150°F	+5	FULL	850	1900	89.5°F	52 PPM	Mdd 0	
7-18	0830	117.2	12.0	27.6	76.3°F	06	150°F	+5	FULL	850	2100	79.3°F	58 PPM	Mdd 0	
7-18	0630	118.2	13.0	85%	79.6⁴F	06	150°F	+5	FULL	850	2050	88.5°F	42 PPM	Mdd 0	
7-18	1030	119.2	14.0	78 x	83.3°F	06	150°F	-5	FULL	850	2050	93.5°F	Mdd 77	Mdd 0	
7-18	1130	120.2	15.0	79%	81.0°F	06	150°F	+5	FULL	850	2100	89.8°F	50 PPM	Wdd 0	
7-18	1230	121.2	16.0	75%	83.4°F	06	150°F	45	FULL	850	2050	91.9*F	48 PPM	Mdd 0	
7-18	1330	122.2	17.0	272	84.3°F	06	150°F	+5	FULL	850	2100	93.9°F	Wdd 95	Mdd 0	
7-18	1430	123.2	18.0	73%	86.0°F	06	150°F	+5	FULL	850	2100	95.6°F	54 PPM	Wdd 0	
)							
	-														
0700 (0730 (AIR PF AIR PF AVERAC	ALIBRATE RECESSED COCESSED COC	0700 CALIBRATED CARBON MONOXIDE MONITO 0730 CHARGE RATE WAS TAKEN. IT TOOK AIR PROCESSED 7-18 = 22.8 CFM X 8 X 64 AIR PROCESSED TO DATE = 10944 CF + 110 AVERAGE TEMPERATURE FOR 7-18 = 81.4°F	N MONOXII TAKEN. 22.8 CFM = 10944 OR 7-18	0700 CALIBRATED CARBON MONOXIDE MONITOR 0730 CHARGE RATE WAS TAKEN. IT TOOK 15.7 MINUTES AIR PROCESSED 7-18 = 22.8 CFM X 8 X 60 = 10944 AIR PROCESSED TO DATE = 10944 CF + 11007 CF = 2199 AVERAGE TEMPERATURE FOR 7-18 = 81.4*F	TES 2195	HARGE FROM '	TO CHARGE FROM 1000 PSIG TO 2000 PSIG 1 TOTAL CUBIC FEET	000 PSIG	COMMENTS	STUZ					

A-3

180N MONOXIDE ORE AFTER TER FILTER 10 PPM 0 PPM 1-2 PPM 1-2 PPM 1-2 PPM 1-2 PPM 1-2 PPM 1-2 PPM 1-2 PPM
48 PPM 48 PPM 48 PPM 52 PPM 46 PPM 46 PPM 54 PPM
COMPRESSOR DISCHARGE LINE LINE LINE LINE LINE TEMPERATURE 050 779.2°F 50 87.8°F 54 95.3°F 95.3°F 56 PKESSURE TEMPERATURE 55 695.3°F 56 PKESSURE TEMPERATURE 55 695.3°F 56 PKESSURE TEMPERATURE 55 695.3°F 56 PKESSURE TEMPERATURE 55 FKEST
1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
1X A .0G EL MOUNTED EM EVALUATION AGE OIL 850 FULL 850 FULL 850 FULL 850 FULL 850 FULL 850 FULL 850 OVER EXPECTED 1
APPENDI) 1 TEST 10 2 PANEL 3 V STER
SURE ENGINE HEAD 150°F 150°F
ATURE PRESSURE 90 150
##
18.0 89.0% 19.0 82% 20.0 96% 22.0 70% 4.0 72% 4.0 72% 6.0 66% 110E HOWITOR - 82.3 *F 51NE. ADDED 1 P 17 TOOK 15.4 M19 17 TOOK 15.4 M19 18 4.0 = 11184, 10 18 4.0 = 11184, 10 18 5.0 = 11
REAL TOTAL HOURS H
1991 REAL TOTAL TOTAL AMBIENT AMBIENT TOTAL AMBIENT AMBIENT TOTAL AMBIENT TEST WAS 133% OF "CORRECTED" TOTAL TOTAL AMBIENT TEST WAS 133% OF "CORRECTED" TOTAL TOTAL AMBIENT TEST WAS 133% OF "CORRECTED" TOTAL TEST WAS 133% OF "CORRECTED" TOTAL TOTAL TEST WAS 133% OF "CORRECTED" TOTAL TO
ANERA ANERA 1035 1014L

Memorandum

Ç.

17 July 1991

To: Dave Sullivan, NEDU From: G. Deason, Code 5130

Subject: Analysis of air sample from NEDU test #91-24. Bauer

P-2 panel mounted purification system evaluation.

Two hour sample.

1. In accordance with your request, the air sample delivered to the gas analysis lab was analyzed and found to contain:

Component	Sample
Oxygen	21%
Nitrogen	78.1%
Argon	0.9%
Carbon Dioxide	439 PPM
Carbon Monoxide	<0.5 PPM
Total Hydrocarbons*	2.3 PPM
Total Halogens**	<0.5 PPM
Methane	2.3 PPM
Acetylene	<0.1 PPM
Acetone	<0.1 PPM
Freon 113	<0.1 PPM
Methyl Ethyl Ketone	<0.1 PPM
Ethylene	<0.1 PPM
Toluene	<0.1 PPM
Benzene	<0.1 PPM
Formaldehyde	<0.1 PPM
C4+	<0.1 PPM

^{*}Expressed as methane equivalents.

2. The above sample showed no appreciable contamination; all components were within the acceptable range of the U.S. Navy Diver's Air Purity Standards.

Glen Deason Chemist

^{**}Expressed as methyl chloride equivalents.

APPENDIX B

Memorandum

19 July 1991

To: Dave Sullivan, NEDU From: G. Deason, Code 5130

Subject: Analysis of air sample from NEDU test #91-24. Bauer

P-2 panel mounted purification system evaluation.

. Fifteen hour sample.

1. In accordance with your request, the air sample delivered to the gas analysis lab was analyzed and found to contain:

Component	Sample
Oxygen	21%
Nitrogen	78.1%
Argon	0.9%
Carbon Dioxide	496 PPM
Carbon Monoxide	1.6 PPM
Total Hydrocarbons*	1.6 PPM
Total Halogens**	<0.5 PPM
Methane	1.6 PPM
Acetylene	<0.1 PPM
Acetone	<0.1 PPM
Freon 113	<0.1 PPM
Methyl Ethyl Ketone	<0.1 PPM
Ethylene	<0.1 PPM
Toluene	<0.1 PPM
Benzene	<0.1 PPM
Formaldehyde	<0.1 PPM
C4+	<0.1 PPM

^{*}Expressed as methane equivalents.

2. The above sample showed no appreciable contamination; all components were within the acceptable range of the U.S. Navy Diver's Air Purity Standards.

Glen Deason Chemist

^{**}Expressed as methyl chloride equivalents.

Memorandum

22 July 1991

To: Dave Sullivan, NEDU

From: Glen Deason, Code 5130

Subject: Analysis of Air Sample from NEDU test #91-24. Bauer

P-2 panel mounted purification system evaluation.

Twenty five hour sample.

1. In accordance with your request, the air sample delivered to the gas analysis lab was analyzed and found to contain:

Component	Results
Oxygen	21%
Nitrogen	78.1%
Argon	0.9%
Carbon Dioxide	365 PPM
Carbon Monoxide	46.0 PPM
Total Hydrocarbons*	1.6 PPM
Total Halogens	(0.5 PPM
Methane	1.6 PPM
Ethane	<0.1 PPM
Acetone	<0.1 PPM
Acetylene	<0.1 PPM
Methyl Ethyl Ketone	<0.1 PPM
Freon 113	<0.1 PPM
Benzene	<0.1 PPM
Toluene	<0.1 PPM
C4+	<0.1 PPM

*Expressed as methane equivalents

2. The above sample showed appreciable contamination; all components were not within the acceptable range of the USN Diver's Air Purity Standards.

Glen Deason Chemist